

WALL TYPE LEGEND

A 3/4" METAL STUDS @ 16" O.C. W/ 5/8" GPDW EA. SIDE, TIGHT TO DECK BOTH SIDES, W/ SOUND BATT INSULATION.

B 3/4" METAL STUDS @ 16" O.C. W/ 5/8" GPDW EA. SIDE, ONE SIDE GPDW TO DECK, ONE SIDE GPDW TO 6" ABOVE CEILING, W/ SOUND BATT INSULATION.

C 5" METAL STUDS @ 16" O.C. W/ SOUND BATT INSULATION; NON-FIXTURE SIDE 1/2" GPDW TO DECK, FIXTURE SIDE 5/8" GREEN GPDW & CERAMIC TILE TO 4'-0" A.F.F., 5/8" GPDW 4'-0" A.F.F. TO 6" ABOVE CEILING.

C1 (2) 3/4" METAL STUDS @ 16" O.C. W/ SOUND BATT INSULATION; NON-FIXTURE SIDE 1/2" GPDW TO DECK, FIXTURE SIDE 5/8" GREEN GPDW & CERAMIC TILE TO 4'-0" A.F.F., 5/8" GPDW 4'-0" A.F.F. TO 6" ABOVE CEILING.

D 3/4" METAL STUDS @ 16" O.C. W/ SOUND BATT INSULATION; NON-FIXTURE SIDE 1/2" GPDW TO DECK, FIXTURE SIDE 5/8" GREEN GPDW & CERAMIC TILE TO 4'-0" A.F.F., 5/8" GPDW 4'-0" A.F.F. TO 6" ABOVE CEILING.

E 3/4" METAL STUDS @ 16" O.C. 5/8" GREEN GPDW & CERAMIC TILE TO 4'-0" A.F.F., 5/8" GPDW 4'-0" A.F.F. TO 6" ABOVE CEILING, BOTH SIDES.

F 3/4" METAL STUDS @ 16" O.C. W/ SOUND BATT INSULATION, FIXTURE SIDE 5/8" GREEN GPDW & CERAMIC TILE TO 4'-0" A.F.F., 5/8" GPDW 4'-0" A.F.F. TO 6" ABOVE CEILING.

G 5" METAL STUDS @ 16" O.C. W/ SOUND BATT INSULATION; 5/8" GREEN GPDW & CERAMIC TILE TO 4'-0" A.F.F., 5/8" GPDW 4'-0" A.F.F. TO 6" ABOVE CEILING, BOTH SIDES.


H 3/4" METAL STUDS @ 16" O.C. W/ 5/8" GPDW EA. SIDE, 6" ABOVE CEILING.

J EXISTING WALL

NOTE:

1. PROVIDE BLOCKING IN WALLS AND CEILING AS REQUIRED FOR ALL WALL/CEILING MOUNTED ITEMS.
2. COORDINATE ALL NECESSARY WALL OPENINGS & PENETRATIONS WITH MECHANICAL & ELECTRICAL SUBCONTRACTORS.
3. MINIMUM METAL STUD GA. = 20 GA.
4. PROVIDE CONTROL JOINTS IN DRYWALL PER THE MOST STRINGENT; USG "GYPSUM CONSTRUCTION HANDBOOK", ASTM C 840, AND THE GYPSUM ASSOCIATION STANDARD GA-216. PROVIDE CONTROL JOINTS AT DOORS & WINDOWS, CORNERS TO FLOOR OR UNDERSIDE OF TRUSSES. PROVIDE AT A MINIMUM OF 30" ON CENTER ON WALLS OVER 30'.
5. PROVIDE A MIN. LEVEL 4 DRYWALL FINISH IN CONJUNCTION WITH PAINTING CONTRACTOR.
6. PROVIDE ACOUSTICAL SEALANTS.
7. PROVIDE ALL REQUIRED FIRE-STOPPING & SMOKE MATERIALS AT TOP & BOTTOM OF WALLS AS REQUIRED.
8. INSTALL HOLLOW METAL DOOR & BORROWED LIGHT FRAMES IN METAL STUD/DRYWALLS. INCLUDE SPOT GROUTING.
9. PROVIDE SOUND BATT INSULATION AT INTERIOR WALLS.
10. PATCH DRYWALL AT DEMO LOCATIONS.
11. MISC. TOUCH UP AT EXISTING DRYWALL. SKIM WHERE VINYL WALL COVERING IS REMOVED.
12. PROVIDE FIRE-STOPPING AS REQUIRED.

FIRST FLOOR PLAN
1/8" = 1'-0"



CARPE DIEM - NORTHWEST
5435 W. PIKE RD.
INDIANAPOLIS, IN 46254

REVIEW	04.17.15
REVIEW	04.27.15
PROGRESS	05.05.15
BID/PERMIT	05.12.15
CONST.	06.05.15

DRAWN BY: IOC
CHECKED: DSH

FIRST FLOOR PLAN

PROJECT No. 150326